

**Revised BOQ**

S.no	Items	Unit	Qty	Rate	Amount
1	Providing and fixing Granite stone work on lift entry openings such as jambs/floor/soffits as directed by the engineer incharge, with 18mm thick Granite of approved shade (sample of Granite shall be approved by Engineer-In-Charge) over 20mm (average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand ) laid and jointed with grey cement slurry including rubbing and polishing, including edge polishing to match existing granite cladding work. No extra shall be paid for any supporting, shuttering and scaffolding work including jointed with grey cement slurry.				
1.1	a) Granite of any colour and shade ( As per existing pattern)	sqm	15		
2	Providing and fixing Marble stone work on lift entry openings such as jambs/floor/soffits as directed by the engineer incharge, with 18mm thick Granite of approved shade (sample of Granite shall be approved by Engineer-In-Charge) over 20mm (average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand ) laid and jointed with grey cement slurry including rubbing and polishing, including edge polishing to match existing granite cladding work. No extra shall be paid for any supporting, shuttering and scaffolding work including jointed with grey cement slurry.				
2.1	a) Raj Nagar Plain white marble/ Udaipur green marble( As per existing pattern)	sqm	10		
3	Providing and fixing Granite stone flooring with 18mm thick Granite of approved shade (sample of Granite shall be approved by Engineer-In-Charge) and jointed with silicon sealant and adhesive as required for flooring of lift car floor, including rubbing and polishing complete with. The pattern of the flooring shall be matched with the existing flooring in the adjacent lift/s :-				
31	a) Granite of any colour and shade ( As per existing pattern)	sqm	25		
4	Fixing of existing 18mm thick Granite stones on lift entry openings such as jambs/floor/soffits, including cutting of stones to the required size, as directed by the engineer incharge, using 20mm (average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand ) laid and or fixed on jambs and soffits with supporting arrangements and soffit stones anchored to the top of the jambs stones with mortar complete. No extra shall be paid for any supporting, shuttering and scaffolding work including jointed with grey cement slurry.				
4.1	a) Granite of any colour and shade ( As per existing pattern)	sqm	65		
5	Fixing of existing 18mm thick Marble stones on lift entry openings such as jambs/floor/soffits, including cutting of stones to the required size, as directed by the engineer incharge, using 20mm (average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand ) laid and or fixed on jambs and soffits with supporting arrangements and soffit stones anchored to the top of the jambs stones with mortar complete. No extra shall be paid for any supporting, shuttering and scaffolding work including jointed with grey cement slurry.				
5.1	a) Raj Nagar Plain white marble/ Udaipur green marble( As per existing pattern)	sqm	40		
	<b>Total</b>				
	<b>GST @ 18%</b>				
	<b>Total Amount with GST</b>				
	<b>Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory completion of work. Contractor must visit site before quoting and fully satisfy himself of the site conditions.</b>				

In words \_\_\_\_\_