



F.no-IIIT-D/Bldg Proj/Operations/Civil/315/2022

Dated: 25.02.2025

NOTICE INVITING QUOTATION (NIQ-04/2025)

Sealed item rate quotations are invited in **two envelope** system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **Providing and Installation of MS Poles and Civil Foundation Works for the Installation of 10 Additional Flags at IIITD Campus**, so as to reach the office of the undersigned upto **3.00 PM** on **4th Mar 2025** in envelope to be opened on the same day at **3.30 PM**, in the office of the PE & EO, A-203 2nd Floor of old Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Earnest Money Deposit: Rs **1360/-** (Rupees One Thousand Three Hundred Sixty only) is to be submitted with document as earnest money in favour of “**IIIT Delhi Collections**” (except for those who are exempted by NSIC certifications (with Proof)) failing shall be treated as invalid and shall be liable for rejection. This will be enclosed in **Envelope- I. Note: MSME firms are exempted from EMD.**

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 30 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ.
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. **Contractor must visit site before quoting and fully satisfy himself of the site conditions.**
6. Contractor must possess valid GST, PAN, and TIN no.
7. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity, water supply and all other labor, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
8. **Eligibility Criteria:** The agencies must have satisfactory executed **Civil works** in Govt Deptts/PSU/Reputed Pvt sector /MNCs three works each of value Rs 0.27 Lac or two works each of Rs 0.40 Lac or one work of Rs 0.55 Lac during last 7 years. The applications not supported with requisite experience certificates/work order shall not be entertained. This will be enclosed in **Envelope- I**
9. The financial bid of the tenderers, whose technical bid is found to be suitable, will be opened in the presence of the tenderers, who desire to attend the opening of financial bid.
10. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be



enclosed in **Envelope- II**.

11. Payment shall be made as per actual quantities of executed works against RA/Final bill at all locations as directed
12. Security Deposit / Retention money shall be Two and Half percent (2.5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. retention money will be released with Employer until the Defects Liability period is successfully over.
13. Defect Liability period 12 months from date of completion.
14. Protection and maintenance of existing services & Provision for all safety measures for traffic, pedestrian workmen, machinery etc. as considered necessary by the Engineer-in-charge.
15. Conditional offers will not be accepted. The offer shall remain valid for 60 days. The rates shall remain firm for a period of one year from date of award. The work order may be extended to cover additional areas at same rates as per institute requirements. No variation in rates shall be applicable.
16. Rates to quoted are inclusive of all taxes, duties, cartage, loading unloading and shifting to location as called for
17. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
18. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
19. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
20. Contractor will ensure proper clearance of malba/ rubbish / debris created due to the works and clear site following completion of the works.
21. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.

PE & EO



List of Approved Make :

1. Cement - ACC, ULTRATECH, SHREE , BIRLA, AMBUJA , J.K..
2. Reinforcement - SAIL, TISCO, RINL, JSPL. JSW
3. Structural Steel and Roof sheets - SAIL, TISCO, RINL, JSPL, JSW
4. Anchor fastner - HILTI, FISCHER, BOSCH, CANON
5. Nuts, Bolts and screws - KUNDAN, PRIYA, ATUL, PUJA
6. Epoxy paint - M/s Asian Paints Ltd , M/s Berger Paints India Ltd, M/s ICI India Ltd.

**BOQ**

S no.	Items	Unit	Quantity	Rate	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	Kg	206		
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	2		
3	Centering and shuttering including strutting, propping etc. and removal of form work for foundation of poles.	Sqm	10		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	70		
5	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work.	Sqm	10		
	Total				
	GST @ 18%				
	Total Amount with GST				

Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory completion of work.

In words _____