INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI



(A state university established by Govt. of NCT of Delhi)

Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: http://www.iiitd.ac.in

Dated: 12.03.2025

F.no- IIITD/GA/Civil Work/ 2013/24/Part-II

NOTICE INVITING QUOTATION (NIQ-05/2025)

Sealed item rate quotations are invited in **two envelope** system for the following work on behalf of the Registrar IIIT Delhi from Experienced, Eligible and Reputed Specialized Contractors for **Shading works** at outer area of Library block at IIITD Campus, so as to reach the office of the undersigned upto 3.00 PM on 19th Mar 2025 in envelope to be opened on the same day at 3.30 PM, in the office of the CE, A-203 2nd Floor of old Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Earnest Money Deposit: **Rs 5500/-** (Rupees Five Thousand Five Hundred only) is to be submitted with document as earnest money in favour of "**HIT Delhi Collections**" - The bidders having valid registration with NSIC/MSME may avail exemption from submission of EMD and tender fee but must enclose valid NSIC / MSME certificate/document with registration for similar works in envelope No. 1 instead of EMD demand draft. However, all bidders irrespective of their registration with NSIC/MSME have to submit the requisite Tender Fee).

Location – Ground floor of Library Block

- 1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
- 2. **Time Allowed**: 30 days from issue of work order.
- 3. Schedule of quantity: As per enclosed BOQ.
- 4. Clause 12 of GCC CPWD is applicable for EI/SI.
- 5. Contractor must visit site before quoting and fully satisfy himself of the site conditions.
- 6. Contractor must possess valid GST, PAN, and TIN no.
- 7. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity, water supply and all other labor, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
- 8. Eligibility Criteria: The agencies must have satisfactory executed **Civil works** in Govt Deptts/PSU/Reputed Pvt sector /MNCs three works each of value Rs 1.05 Lac or two works each of Rs 1.57 Lac or one work of Rs 2.09 Lac during last 7 years. The applications not supported with requisite

INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI



(A state university established by Govt. of NCT of Delhi)

Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: http://www.iiitd.ac.in

experience certificates/work order shall not be entertained. This will be enclosed in Envelope- I

- 9. The financial bid of the tenderers, whose technical bid is found to be suitable, will be opened in the presence of the tenderers, who desire to attend the opening of financial bid.
- 10. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be enclosed in **Envelope-II**.
- 11. Payment shall be made as per actual quantities of executed works against RA/Final bill at all locations as directed
- 12. Security Deposit / Retention money shall be Two and Half percent (2.5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. retention money will be released with Employer until the Defects Liability period is successfully over.
- 13. Defect Liability period 12 months from date of completion.
- 14. Protection and maintenance of existing services & Provision for all safety measures for traffic, pedestrian workmen, machinery etc. as considered necessary by the Engineer-in-charge.
- 15. Conditional offers will not be accepted. The offer shall remain valid for 60 days. The rates shall remain firm for a period of one year from date of award. The work order may be extended to cover additional areas at same rates as per institute requirements. No variation in rates shall be applicable.
- 16. Rates to quoted are inclusive of all taxes, duties, cartage, loading unloading and shifting to location as called for
- 17. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
- 18. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
- 19. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
- 20. All workers are supposed to use identified utilities of the Institute only.
- 21. Contractor will ensure proper clearance of malba/ rubbish / debris created due to the works and clear site following completion of the works.
- **22.** IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.

PE & EO



INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI

(A state university established by Govt. of NCT of Delhi)

Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: http://www.iiitd.ac.in

BOQ S No Unit Oty Rate Item Description Amount

				Amount
Steel work in built up tubular (round, square or rectangular hollow				
tubes etc.) trusses etc., including cutting, hoisting, fixing in position				
Hot finished welded type tubes	KG	579		
Earth work in excavation and Demolishing cement concrete including Kota stone flooring by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by	CUM	1		
Engineer-incharge.				
Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:	SQM	31		
Two or more coats on new work				
Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	CUM	1		
including necessary fixing arrangements.	sqm	77		
•				
Total Amount with GST				
Note: All rate to be inclusive cost of Transportation, Labour,				
Materials, loading, unloading etc. as required for satisfactory				
completion of work. Contractor must visit site before				
	tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes Earth work in excavation and Demolishing cement concrete including Kota stone flooring by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources) Providing and fixing of awning of Polyster Fabric (0.5 mm thick) including necessary fixing arrangements. Make- SRF or equivalent Total GST @ 18% Total Amount with GST Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory	tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes KG Earth work in excavation and Demolishing cement concrete including Kota stone flooring by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources) Providing and fixing of awning of Polyster Fabric (0.5 mm thick) including necessary fixing arrangements. Make- SRF or equivalent Total GST @ 18% Total Amount with GST Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory completion of work. Contractor must visit site before	tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes Earth work in excavation and Demolishing cement concrete including Kota stone flooring by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources) Providing and fixing of awning of Polyster Fabric (0.5 mm thick) sqm 77 including necessary fixing arrangements. Make- SRF or equivalent Total GST @ 18% Total Amount with GST Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory completion of work. Contractor must visit site before	tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes Earth work in excavation and Demolishing cement concrete including Kota stone flooring by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources) Providing and fixing of awning of Polyster Fabric (0.5 mm thick) including necessary fixing arrangements. Make- SRF or equivalent Total GST @ 18% Total Amount with GST Note: All rate to be inclusive cost of Transportation, Labour, Materials, loading, unloading etc. as required for satisfactory completion of work. Contractor must visit site before

In words	S	
----------	---	--